

# **VAPOR INTRUSION, INSPECTION, MONITORING, AND MAINTENANCE WORK PLAN**

**OLYMPIC MEDICAL FACILITY  
5900 FIRST AVENUE SOUTH  
SEATTLE, WASHINGTON**

**AGREED ORDER NO. DE 5348**

**Submitted by:  
Farallon Consulting, L.L.C.  
975 5th Avenue Northwest  
Issaquah, Washington 98027  
Farallon PN: 457-004**

**For:  
Mr. Ron Taylor  
Capital Industries, Inc.  
5801 Third Avenue South  
Seattle, Washington**


November 2, 2009

Prepared by:




**Daniel Caputo  
Project Chemist**

Reviewed by:



**Peter Jewett, L.G., L.E.G.  
Principal**



## TABLE OF CONTENTS

|   |            |
|---|------------|
| <b>ACRONYMS AND ABBREVIATIONS .....</b>   | <b>ii</b>  |
| <b>1.0 INTRODUCTION .....</b>   | <b>1-1</b> |
| 1.1 PURPOSE.....  | 1-1        |
| 1.2 VAPOR INTRUSION INSPECTION, MONITORING, AND<br>MAINTENANCE WORK PLAN ORGANIZATION ..... | 1-1        |
| <b>2.0 SITE DESCRIPTION AND SYSTEM DESIGN .....</b>   | <b>2-1</b> |
| 2.1 SITE DESCRIPTION .....  | 2-1        |
| 2.2 VAPOR INTRUSION MITIGATION WORK PLAN .....  | 2-1        |
| 2.3 VAPOR INTRUSION MITIGATION SYSTEM .....   | 2-1        |
| <b>3.0 INSPECTION, MONITORING, AND MAINTENANCE PROCEDURES</b>                               | <b>3-1</b> |
| 3.1 INSPECTION AND MONITORING .....   | 3-1        |
| 3.1.1 Tenant Inspections.....   | 3-1        |
| 3.1.2 Annual Inspections .....  | 3-2        |
| 3.1.3 Negative Pressure Field Extension Monitoring.....                                     | 3-2        |
| 3.1.4 Air Quality Monitoring.....   | 3-3        |
| 3.2 SYSTEM RE-EVALUATION AND ENHANCEMENT .....  | 3-3        |
| 3.3 SYSTEM MAINTENANCE .....  | 3-3        |
| 3.4 SYSTEM SHUTDOWN.....  | 3-4        |
| <b>4.0 REPORTING .....</b>  | <b>4-1</b> |
| <b>5.0 BIBLIOGRAPHY .....</b>   | <b>5-1</b> |

## FIGURES


- Figure 1 *Vicinity Map*  
Figure 2 *Location Map for Capital Industries Interim Vapor Intrusion Activities*  
Figure 3 *Olympic Medical Facility Sump, Test Hole, and Air Sample Locations*

## TABLE

- Table 1 *Summary of Inspection and Monitoring Tasks*

## APPENDICES


- Appendix A City of Seattle Permit Application  
Appendix B Pressure Gauge Schematic



Appendix C    Reminder Notice to Tenants


Appendix D    Depressurization System Monitoring Log Book

Appendix E    Inspection Form



## ACRONYMS AND ABBREVIATIONS

|                      |  |
|----------------------|--|
| Agreed Order         | Agreed Order No. DE 5348 between the Washington State Department of Ecology and Capital Industries, Inc.                                     |
| Capital              | Capital Industries, Inc.   |
| COPCs                | constituents of potential concern  |
| Ecology              | Washington State Department of Ecology   |
| Farallon             | Farallon Consulting, L.L.C.  |
| IPIM                 | Inhalation Pathway Interim Measures  |
| IPIMALs              | Inhalation Pathway Interim Measures Action Levels  |
| PFE                  | Negative Pressure Field Extension  |
| PSC                  | Philip Services Corporation  |
| SSDS                 | Sub-Slab Depressurization System   |
| VI Mitigation System | Vapor Intrusion Mitigation System  |
| VIA Work Plan        | Vapor Intrusion Assessment Work Plan dated September 2008, prepared by Farallon, Consulting, L.L.C.  |
| VIM Work Plan        | Vapor Intrusion Mitigation Work Plan dated October 2008, prepared by Farallon, Consulting, L.L.C.  |
| VIIMM Work Plan      | Vapor Intrusion, Inspection, Monitoring, and Maintenance Work Plan dated August 2009, prepared by Farallon, Consulting, L.L.C. (this report) |
| VOC                  | volatile organic compounds   |



## **1.0 INTRODUCTION**

Farallon Consulting, L.L.C. (Farallon) has prepared this Vapor Intrusion, Inspection, Monitoring, and Maintenance Work Plan (VIIMM Work Plan) on behalf of Capital Industries, Inc. (Capital) to describe the procedures for inspection, maintenance, and monitoring of the vapor intrusion mitigation system (VI mitigation system) installed at the Olympic Medical facility located at 5900 First Avenue South in Seattle, Washington (Figure 1). The VIIMM Work Plan has been prepared as part of the Remedial Investigation currently being conducted in accordance with Exhibits B and D of Agreed Order No. DE 5348, which was entered into by Capital and the Washington State Department Ecology (Ecology) on January 24, 2008 (Agreed Order).

### **1.1 PURPOSE**

The purpose of the VIIMM Work Plan is to describe the procedures to be used to inspect, monitor, and maintain the VI mitigation system installed in the Olympic Medical facility to prevent migration of vapors with constituents of potential concern (COPCs) from groundwater to indoor ambient air within the building. The inspection, monitoring, and maintenance procedures are consistent with the Inhalation Pathway Interim Measures (IPIM) Work Plan prepared by Philip Services Corporation (PSC) (2002) and the Draft Interim Vapor Intrusion Plan prepared by Arrow et al. (2007), which is provided as Exhibit D of the Agreed Order.

### **1.2 VAPOR INTRUSION INSPECTION, MONITORING, AND MAINTENANCE WORK PLAN ORGANIZATION**

The VIIMM Work Plan has been organized into the following sections: Section 1 presents the VIIMM Work Plan purpose; Section 2 provides a Site description, a summary of the VI Mitigation Work Plan, and an overview of the Olympic Medical facility VI mitigation system design; Section 3 discusses system inspection, monitoring, and maintenance procedures; and Section 4 discusses the reports that will be prepared to describe the results of the inspection, monitoring, and maintenance activities. The documents used in preparation of the VIIMM Work Plan are referenced in Section 5.



## 2.0 SITE DESCRIPTION AND SYSTEM DESIGN

### 2.1 SITE DESCRIPTION

The Olympic Medical facility is located within the Capital Area of Investigation, down-gradient and southwest of the Capital property (Figure 2). Mitigation of vapor intrusion was deemed necessary based on the analytical results of ambient air samples collected by others (PSC 2005a; GeoEngineers Inc. 2006). Farallon evaluated the data collected by others in accordance with the *Vapor Intrusion Assessment Work Plan, Capital Industries, Inc., 5801 Third Avenue South, Seattle, Washington* (Farallon 2008b) (VIA Work Plan). The VI mitigation system was designed according to specifications defined in the *Vapor Intrusion Mitigation Work Plan, Olympic Medical Facility, Seattle, Washington* (Farallon 2008c) (VIM Work Plan); and was installed at the Olympic Medical facility in January 2009. The City of Seattle Department of Planning and Development Mechanical Expedited (Full) Permit Application includes a schematic of the sub-slab depressurization system (SSDS) installed in the Olympic Medical facility and is provided in Appendix A.

### 2.2 VAPOR INTRUSION MITIGATION WORK PLAN

The preparation and design of the VI mitigation system at the Olympic Medical facility was completed in accordance with the VIM Work Plan, which summarized the procedures to be used to mitigate intrusion of vapors with concentrations of volatile COPCs that migrate from groundwater to buildings located within the Capital Site. The VIM Work Plan includes procedures for collecting VI mitigation system design data; preparing the VI mitigation system design; and installing, implementing, and operating the VI mitigation system.

### 2.3 VAPOR INTRUSION MITIGATION SYSTEM

The VI mitigation system addressed in this VIIMM Work Plan includes the SSDS installed at the Olympic Medical facility. The VI mitigation system is designed to maintain negative pressure directly beneath the building, thereby acting as a “sink” for soil vapors in the vicinity of the structure. The VI mitigation system installed at the Olympic Medical facility was designed and installed by Advanced Radon Technologies and began operation on January 23, 2009.

Prior to installation of the VI mitigation system, diagnostic testing was conducted at the Olympic Medical facility to determine the layout and number of sump locations necessary to depressurize the warehouse and manufacturing areas of the facility. The results of the diagnostic testing determined that seven sump locations connected to one exhaust fan that discharges through one exhaust stack would be adequate for the mitigation system at the Olympic Medical facility (Farallon 2009a). Schematics of the SSDS design and layout are provided in Appendix A. A detailed discussion of the VI mitigation system design is presented in the *Vapor Intrusion Mitigation Design Plan, Olympic Medical Facility* dated March 9, 2009, prepared by Farallon (2009a).



A total of seven sumps, each consisting of a 5-inch-diameter boring directly above a 10- to 20-gallon sub-slab cavity, were installed during the diagnostic testing phase. A schematic of each sump location is presented on Sheet No. M4 of Appendix A. Risers and piping connect each sump to the exhaust fan, which is mounted on the roof of the Olympic Medical facility. Risers are seated on a rubber seal within the sump, sealed with waterproof sealant, and extend from the sump located at and below ground level through the ceiling and/or roof. Each location where risers penetrate the roof is sealed with roof flashing and waterproof sealant. The specific details for each riser are presented on Sheet No. M4 of Appendix A.


Piping connects the risers to the exhaust fan mounted on the roof of the Olympic Medical facility. All of the piping forms one network and is positioned so the connection to the exhaust fan is at the highest point of the network and the connection to each riser is at the lowest point of the network. Piping is angled to prevent water vapor from condensing into pools at low spots within the piping. Piping specifications are presented on Sheet No. M3 of Appendix A.

A Rotron DR656K72X 3-horsepower regenerative exhaust fan manufactured by Ametek Technical and Industrial Products provides the suction to the sumps via the risers and piping of the mitigation system. The specifications for the exhaust fan were determined by Advanced Radon Technologies based on information collected during the diagnostic testing conducted at the Olympic Medical facility (Farallon 2009a). The exhaust fan is mounted to a raised platform on the roof of the Olympic Medical facility. Vibration isolators are used between the exhaust fan and the platform to prevent roof vibration and excess noise. The exhaust fan is connected and sealed to the piping and the exhaust stack. The regenerative blower schedule presents the specific details of the exhaust fan on Sheet No. M4 of Appendix A.

The exhaust stack is constructed of stainless steel and polyvinyl chloride (PVC) that effectively extends the point of emission to a height of approximately 7 feet above roof level. The exhaust stack outlet is angled and cut on the vertical to prevent precipitation from entering the exhaust stack while continuing to exhaust emissions. A schematic showing the specific details of the exhaust stack are presented on Sheet No. M4 of Appendix A.

A pressure gauge was installed at each riser to measure and confirm that negative pressure is being applied throughout the mitigation system. Previously constructed systems in the area have included manometer on each leg of the system to monitor system performance; however, due to the size of the Olympic Medical facility, subsurface conditions, the riser and piping network, and the fan, system pressure exceeds the limits of the commonly used manometer. Therefore, a Magnehelic pressure gauge rather than a manometer is used to measure system pressure. A valve system was installed to enable disconnection of pressure gauges during non-monitoring events.

The pressure gauge and valve system was mounted to the riser with flexible tubing. A main valve was installed between the riser and the pressure gauge to regulate the pressure applied to the gauge from the riser. A relief valve was installed to control the pressure between the first valve and the pressure gauge. The relief valve can open the pressure gauge to ambient air pressure during non-monitoring events and relieve the pressure within the tubing after the main valve has been closed. The main valve will remain closed and the relief valve will remain open



when the VI monitoring system is not operating. During VI system monitoring events, the main valve will be opened and the relief valve will be closed to activate the pressure gauge. The pressure gauge will provide confirmation that negative pressure is being applied by the exhaust fan to the subsurface via each riser. The negative pressure applied by the exhaust fan will not allow soil gas removed from the subsurface to enter indoor air. Opening the relief valve will allow indoor air to enter the tubing, thereby relieving negative pressure remaining in the pressure gauge when it is not in use. A schematic of the pressure gauge and valve set-up, as well as the product literature and specifications associated with the devices, is included in Appendix B.





### 3.0 INSPECTION, MONITORING, AND MAINTENANCE PROCEDURES

This section presents the inspection and monitoring procedures to be conducted by Capital at the Olympic Medical facility, the protocols for evaluating and enhancing VI mitigation system effectiveness, system operation and maintenance, and guidelines to shut down the VI mitigation system. The inspection and monitoring activities were developed based on and will be conducted in accordance with the *Verification of Depressurization System Effectiveness and Long-Term Operation and Maintenance Plan for Inhalation Pathway Interim Measures* developed for the PSC (2005b) Georgetown Facility. Monitoring procedures at the Olympic Medical facility will be conducted parallel to the groundwater monitoring conducted at the Capital Site as part of the Capital Remedial Investigation. Table 1 provides a summary of inspection and monitoring tasks and the frequency at which they will occur.

#### 3.1 INSPECTION AND MONITORING

Periodic inspection and monitoring will be conducted during operation of the VI mitigation system to confirm that the Olympic Medical facility SSDS is operating effectively. The inspections and monitoring will be conducted by Capital until inspection and monitoring responsibilities have been transferred to a separate entity with Ecology approval. Formal inspection and monitoring of the VI mitigation system will include the following:

- Annual system inspection;
- Biannual negative pressure field extension (PFE) monitoring, and
- Biannual air quality monitoring.

##### 3.1.1 Tenant Inspections

Tenant inspections will be conducted on a monthly basis to ensure that the SSDS is operating properly. During inspections, the tenants will conduct a check of each riser pressure gauge that is accessible. Capital will send a monthly reminder to the tenant at the Olympic Medical facility to prompt the recipients to check the pressure gauges to confirm that the VI mitigation system is operating properly. The current tenants of the Olympic Medical facility have agreed to perform inspections. Inspections will be documented in an inspection log book located at the Olympic Medical facility. The Reminder Notice to Tenants is provided in Appendix C. An example of the Log Book located at the Olympic Medical facility is provided in Appendix D.

If the SSDS system is not operating properly, Olympic Medical facility tenant will contact Capital and/or Farallon. Contact information for the Olympic Medical facility, Capital, and Farallon is provided below.

- Olympic Medical  
Ms. Lana Hauge, Operations Manager  
5900 First Avenue South  
Seattle, Washington 98108  
(206) 268-5166



- Capital Industries, Inc.  
Mr. Ray Carr, Plant Manager  
5801 Third Avenue South  
Seattle, Washington 98108  
(206) 762-8585
- Farallon Consulting, L.L.C.  
Mr. Daniel Caputo, Project Chemist  
975 5<sup>th</sup> Avenue Northwest, Suite 100  
Issaquah, Washington 98027  
(425) 295-0800

### **3.1.2 Annual Inspections**

Annual inspections will be conducted to observe and document the condition of the SSDS and to record changes to the Olympic Medical facility and surrounding area that could affect the SSDS performance. To the extent feasible, annual inspections will be conducted at the same time of year to facilitate documenting inspection results in a single submittal. The Sub-Slab Depressurization System Inspection Form presented in Appendix E will be used to document the annual inspections.

The annual inspection will consist of observing and documenting the condition of VI mitigation system components and any structural changes or modifications to the Olympic Medical facility and adjacent buildings and structures, and recording the pressure gauge measurements at each of the seven sumps at the Olympic Medical facility. The pressure gauge measurements previously documented on the Sub-Slab Depressurization System Inspection Form will be used for comparison during the inspection. Photographs will be taken during the inspection to document any deterioration of materials (e.g., cracks in piping, mounting damage) and other pertinent changes in the condition of the VI mitigation system, the building structure, or other factors that could impact system operation and effectiveness.

### **3.1.3 Negative Pressure Field Extension Monitoring**

PFE monitoring will be conducted at the Olympic Medical facility on a biannual basis during the heating season to measure the pressure differential across the building slab while the VI mitigation system is operating. The results of the PFE monitoring will be used to confirm that the negative pressure field extends to points far removed from the sump locations. The 10 test holes located throughout the slab of the Olympic Medical facility will be used for the PFE monitoring to determine the radius of influence of each sump. A negative pressure of 0.005 inches of water column or more at each of the test holes is considered acceptable. The test holes will be plugged between monitoring events to maintain the integrity of the depressurization applied by the mitigation system.



### 3.1.4 Air Quality Monitoring

Air quality monitoring will be conducted on a biannual basis in conjunction with biannual PFE monitoring. A site-specific Sampling and Analysis Plan (SAP) will be prepared to guide the air quality monitoring and will specify the number of air samples to be collected, sampling locations, and related air monitoring criteria. A draft SAP will be submitted to Ecology for review at least 30 days prior to the scheduled sampling event. Air quality monitoring, evaluation of results, and comparison with indoor air IPIM action levels (IPIMALs) will be conducted in accordance with the methodology specified in the VIA Work Plan.

An SAP relative to air quality monitoring will be submitted at least 30 days prior to the scheduled monitoring event. The air quality monitoring SAP will provide the sampling and analysis procedures to be conducted during each biannual air quality monitoring event.

## 3.2 SYSTEM RE-EVALUATION AND ENHANCEMENT

The results of air quality monitoring, PFE monitoring, groundwater monitoring, and/or annual inspections will be evaluated to determine whether modifications to the VI mitigation system are necessary. The VI mitigation system will be re-evaluated or modified to enhance effectiveness, if warranted, based on inspection and monitoring results. The following criteria will be used to determine whether re-evaluation of the VI mitigation system is warranted:

- Inspection results indicate a significant structural change in the Olympic Medical facility (e.g., remodeling that could introduce additional pathways for vapor intrusion);
- Air quality monitoring results indicate an indoor air IPIMAL exceedance; and/or
- Groundwater sampling analytical results indicate a minimum tenfold increase in cumulative VI risk/hazard, as defined in the VIA Work Plan, in the vicinity of the Olympic Medical facility.

The scope of work to re-evaluate and, if necessary, enhance VI mitigation system effectiveness will be provided on a case-by-case basis and discussed with Ecology. If a significant structural change is observed in the Olympic Medical facility or if the analytical results for groundwater samples indicate a significant increase in volatile organic compounds (VOC) concentrations, Capital will contact Ecology within 3 weeks of the building inspection date or receipt of analytical results.

## 3.3 SYSTEM MAINTENANCE

VI mitigation system maintenance will be performed on an as-needed basis following the first year of operation, and will be based on conditions observed during the annual inspections or on reports from the Olympic Medical facility tenant. Components that may require maintenance include the exhaust fan, pressure gauges, and piping. The exhaust fan is not amenable to periodic maintenance and is relatively easy to replace. Therefore, the fan will be operated until excessive noise, vibration, or significantly reduced pressure gauge readings are noted, at which point the fan will be repaired or replaced. An operational failure of the fan would be indicated




by pressure gauges that will be checked during monthly tenant inspections and annual inspections.

Pressure gauges are less robust than manometers over continued use and may fail after prolonged use. The pressure gauges were installed on multiple "legs" connecting the exhaust fan to the sub-slab sumps to aid in identification of a failed gauge. With this design, a failed pressure gauge will be identifiable when it is the only gauge not reading the correct system pressure when compared against the other gauges. If a pressure gauge failure is confirmed, a replacement pressure gauge will be installed and tested. If a manometer is identified that can effectively monitor the existing and anticipated pressure ranges, one may be used in place of a pressure gauge.

Replacement of cracked or otherwise damaged system piping observed during annual inspections or identified by the building tenant may be required. Proposed modifications to the SSDS will be presented to Ecology for approval prior to proceeding with the work.

### **3.4 SYSTEM SHUTDOWN**

The analytical results of groundwater monitoring will be evaluated to determine whether continued operation of the SSDS at the Olympic Medical facility is necessary to mitigate migration of VOCs from groundwater to indoor air. The analytical results for the groundwater samples collected from monitoring wells proximate to the Olympic Medical facility will be periodically collected for analysis, and results compared against groundwater IPIMALs. If concentrations of VOCs are below the respective IPIMALs, continued operation of the SSDS at the Olympic Medical facility may not be necessary. Capital will discuss with Ecology the shutdown procedures, public communications, and post-shutdown monitoring requirements when operation of the SSDS at the Olympic Medical facility is deemed no longer necessary.



## 4.0 REPORTING

The results of the SSDS inspections and monitoring at the Olympic Medical facility will be presented in an Annual Report. Each Annual Report will contain a brief narrative of the procedures followed for the inspection, monitoring, and maintenance activities; a copy of completed inspection forms; a summary of pressure gauge readings; the results of PFE monitoring; and the results from air quality monitoring events. Each Annual Report will document potentially significant changes in conditions or other issues observed during the inspections, present supporting photographs, and recommend follow-up investigations and/or corrective actions, if necessary. Each Annual Report will include an evaluation of the most recent groundwater monitoring results to identify changes in VOC concentrations that could trigger re-evaluation of SSDS effectiveness, and to determine when operation of the SSDS may no longer be necessary. Following review and approval by Capital, the Annual Report will be submitted to Ecology for review and comment within 60 days of the annual inspection.

Inspection and monitoring results and any maintenance that occurred during the preceding quarter will be discussed in Quarterly Progress Reports.



## 5.0 BIBLIOGRAPHY

- Arrow Environmental; Aspect Consulting; Farallon Consulting, L.L.C.; and Pacific Groundwater Group (Arrow et al.). 2007. *Draft Interim Vapor Intrusion Plan*. Prepared for the Washington State Department of Ecology. May 1.
- Farallon Consulting, L.L.C. (Farallon). 2008a. *Remedial Investigation Work Plan, Capital Industries, 5801 Third Avenue South, Seattle, Washington*. Prepared for Capital Industries, Inc., Seattle, Washington. September 16.
- . 2008b. *Vapor Intrusion Assessment Work Plan, Capital Industries, 5801 Third Avenue South, Seattle, Washington*. Prepared for Capital Industries, Inc., Seattle, Washington. September.
- . 2008c. *Vapor Intrusion Mitigation Work Plan, Seattle, Washington*. Prepared for Capital Industries, Inc., Seattle, Washington. October.
- . 2009a. *Vapor Intrusion Mitigation Design Plan, Olympic Medical Facility, Seattle, Washington*. Prepared for Capital Industries, Inc., Seattle, Washington. March 9.
- . 2009a. *Vapor Intrusion Mitigation Work Plan, Olympic Medical Facility, Capital Industries, 5801 Third Avenue South, Seattle, Washington*. Prepared for Capital Industries, Inc., Seattle, Washington. March 9.
- GeoEngineers Inc. 2006. *Air Sampling Results (Partial)*. March.
- Philip Services Corporation (PSC). 2002. *Revised Inhalation Pathway Interim Measures Work Plan*. Prepared for the Washington State Department of Ecology. August.
- . 2003. *Supplemental Inhalation Pathway Interim Measures Work Plan*. Prepared for the Washington State Department of Ecology. May.
- . 2005a. *Tier 3 Sampling Report for Inhalation Pathway Interim Measures, 5900 1<sup>st</sup> Avenue South, Seattle, Washington*. January.
- . 2005b. *Verification of Depressurization System Effectiveness and Long-Term Operation and Maintenance Plan for Inhalation Pathway Interim Measures*. April 2005.
- Pioneer Technologies Corporation. 2006. *Summary of the Inhalation Pathway Interim Measure Approach*. Prepared for Philip Services Corporation, Kent, Washington. October.


## **FIGURES**

### **VAPOR INTRUSION, INSPECTION, MONITORING, AND MAINTENANCE WORK PLAN**

Olympic Medical Facility  
5900 First Avenue South  
Seattle, Washington

Farallon PN: 457-004





REFERENCE: 7.5 MINUTE USGS QUADRANGLE SOUTH SEATTLE, WASHINGTON. DATED 1983

0 500

APPROXIMATE SCALE IN METERS



WASHINGTON



FARALLON CONSULTING  
975 5th Avenue Northwest  
Issaquah, WA 98027

## FIGURE 1

VICINITY MAP  
VAPOR INTRUSION, INSPECTION, MONITORING  
AND MAINTENANCE WORK PLAN  
OLYMPIC MEDICAL FACILITY  
SEATTLE, WASHINGTON

FARALLON PN: 457-004


Drawn By: DEW


Checked By: DC

Date: 8/24/09

Disk Reference: FLOORJIM21







## **TABLE**

### **VAPOR INTRUSION, INSPECTION, MONITORING, AND MAINTENANCE WORK PLAN**

Olympic Medical Facility  
5900 First Avenue South  
Seattle, Washington

Farallon PN: 457-004

**Table 1**  
**Summary of Inspection and Monitoring Tasks**  
**Vapor Intrusion Inspection, Monitoring, and Maintenance Work Plan**  
**Olympic Medical Facility**  
**Seattle, Washington**  
**Farallon PN: 457-004**

| <b>Inspection and Monitoring Task</b> | <b>Frequency/Dates</b>                           | <b>Performed by:</b> | <b>Documented In:</b>                  |
|---------------------------------------|--|----------------------|--|
| Check all riser pressures             | Monthly  | Olympic Medical      | Olympic Medical VI Inspection Log Book |
| System inspections                    | Annually; each January                           | Farallon             | VI Annual Report                       |
| PFE tests                             | Biannually; every other January starting 01/2011 | Farallon             | VI Annual Report (when applicable)     |
| Performance air-sampling              | Biannually; every other January starting 01/2011 | Farallon             | VI Annual Report (when applicable)     |

**APPENDIX A**  
**CITY OF SEATTLE PERMIT APPLICATION**

**VAPOR INTRUSION, INSPECTION, MONITORING,  
AND MAINTENANCE WORK PLAN**

Olympic Medical Facility  
5900 First Avenue South  
Seattle, Washington


Farallon PN: 457-004

# OLYMPIC MEDICAL BUILDING

## City of Seattle

### Department of Planning & Development

Olympic Medical Building  
5900 1st. Avenue South  
Seattle, Washington  
98108-3248



MECHANICAL ENGINEER:

MANDATORY CODE COMPLIANCE

- VOC PIPING (VOLATILE ORGANIC COMPOUND)
- CONTINUATION OF PIPING
- TEE DOWN
- TEE UP
- ELBOW DOWN
- ELBOW UP
- EXHAUST FAN

- CAPPED END
- PLAN NOTE
- SECTION DESIGNATION  
SHEET ON WHICH SECTION IS DRAWN
- DETAIL DESIGNATION  
DETAIL NUMBER  
SHEET ON WHICH DETAIL IS DRAWN


- AFF ABOVE FINISHED FLOOR
- BV BALL VENT
- CU CONDENSING UNIT
- EF EXHAUST FAN
- FA FRESH AIR INTAKE
- IE INVERT ELEVATION
- RD ROOF DRAIN
- RV RELIEF VENT
- RTU ROOF TOP UNIT
- TYP TYPICAL
- VOC VOLATILE ORGANIC COMPOUND
- VTR VENT THRU ROOF

- EQUIPMENT AND MATERIAL REMOVED SHALL BECOME PROPERTY OF THE CONTRACTOR UNLESS NOTED OTHERWISE AND SHALL BE REMOVED OFF-SITE.
- DRAWINGS ARE PARTLY DIAGRAMMATIC AND DON'T NECESSARILY SHOW EXACT CONDITIONS OF CONSTRUCTION. LOCATION OF PIPING SHALL BE FIELD VERIFIED TO DETERMINE THAT IT CLEARS ALL OPENINGS AT STRUCTURAL MEMBERS, CHASES AND THAT EQUIPMENT, ETC. HAVING FIXED LOCATIONS WILL BE CLEARED.
- EXAMINE PREMISES AND BECOME FAMILIAR WITH EXISTING CONDITIONS BEFORE STARTING WORK. FIELD VERIFY CONSTRUCTION MATERIALS OF FLOORS, WALLS, CEILINGS AND ROOFS BEFORE STARTING WORK. OTHER EXISTING MATERIALS AND EQUIPMENT ARE NOT SHOWN ON THESE DRAWINGS SUCH AS DUCTWORK, HVAC EQUIPMENT, HEATING PIPING, GAS PIPING, CONDUIT, ETC. THE CONTRACTOR SHALL FIELD VERIFY LOCATIONS AND SIZES OF EXISTING MATERIALS AND EQUIPMENT AND SHALL OFFSET NEW PIPING AS NECESSARY AROUND EXISTING MATERIALS AND EQUIPMENT.
- REMOVE MEANS, REMOVE AND DISPOSE OF UNLESS SPECIFICALLY DIRECTED OTHERWISE.
- DO NOT ALLOW ANY WORK (PIPING/EQUIPMENT) TO BE COVERED UP OR ENCLOSED UNTIL INSPECTED, TESTED AND APPROVED BY AUTHORITY HAVING JURISDICTION AND/OR THE OWNER'S REPRESENTATIVE.
- ALL EQUIPMENT SHALL BE INSTALLED IN STRICT ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS. WHERE CONFLICTS OCCUR, BRING THOSE TO THE ATTENTION OF THE DESIGN ENGINEER IMMEDIATELY AND BEFORE INSTALLING THE PIECE OF EQUIPMENT OR ITEM.
- THE CONTRACTOR SHALL PROVIDE ALL NECESSARY SAW CUTTING AND CORE DRILLING AND PATCHING OF FLOORS, WALLS, CEILINGS AND ROOFS IN ORDER TO INSTALL THE NEW VOC SYSTEMS.
- THE CONTRACTOR SHALL ARRANGE AND PAY FOR ALL PERMITS, INSPECTIONS AND FEES REQUIRED IN CONNECTION WITH THIS PROJECT.

- M-1 COVER SHEET
- M-2 SITE PLAN
- M-3 ROOF PLAN
- M-4 DETAILS & SCHEDULE



RADON MITIGATION TESTING AND INSTALLATION  
NORTH 2801 MONROE, SUITE A  
SPokane, WASHINGTON  
(509) 326-5127



98108-3248

SEATTLE, WASHINGTON

PROJECT:

JOB NO.: 6198563  
DATE: 11/07/08  
DRAWN: KJ  
CHECKED: DG

SHEET NO.:

FRAY EQUIPMENT COMPANY  
PARCEL NUMBER: 1924049078  
ZONING: IG2 U/85

JACK IN THE BOX  
PARCEL NUMBER: 1924049078  
ZONING: IG2 U/85

CHEVRON STATION  
PARCEL NUMBER: 1924049069  
ZONING: IG2U/85

CAPITAL INDUSTRIES  
PARCEL NUMBER: 1722802245  
ZONING: IG2 U/85

CAPITAL INDUSTRIES  
PARCEL NUMBER: 1722802253  
ZONING: IG2 U/85

CAPITAL INDUSTRIES  
PARCEL NUMBER: 1722801820  
ZONING: IG2 U/85

MOBILE CRANE  
PARCEL NUMBER: 2024049054  
ZONING: IG2 U/85

PARCEL NUMBER: 2024049050  
ZONING: IG2 U/85

LEGAL DESCRIPTION:

POR OF GL 3 DAF-BEG AT INTSN S MGM FIDALGO ST & E MGM 1ST AVE S TH  
SLY ALG SD E MGM 300 FT TH ELY PLT S MGM FIDALGO ST 381 FT TH NLY PLT  
E MGM 1ST AVE S 300 FT TO S MGM FIDALGO ST TH WALG ST 381 FT TO BEG

OLYMPIC MEDICAL BUILDING

SCALE: 1" = 30'-0"


HECKWITH AND FUFFEL BUILDING  
PARCEL NUMBER: 2024049043  
ZONING: IG2U/85

LEGEND

— PROPERTY LINE  
— EXTERIOR BUILDING WALL  
IG2 U/85 INDUSTRIAL ZONE CODE



RADON MITIGATION TESTING AND INSTALLATION  
NORTH 2801 MONROE SUITE A  
SPOKANE, WASHINGTON  
(509) 326-5127



98108-3248

SEATTLE, WASHINGTON

PROJECT:

JOB NO.: 6198563

DATE: 11/07/08


DRAWN: KJ

CHECKED: DG

SHEET NO.:



RADON MITIGATION TESTING AND INSTALLATION  
NORTH 2801 MONROE, SUITE A  
SPOKANE, WASHINGTON  
(509) 326-5127



98108-3248


SEATTLE, WASHINGTON

PROJECT: 5195563  
DATE: 11/07/08  
DRAWN: KJ  
CHECKED: DG

SHEET NO.:

SOUTH FIDALGO STREET

1ST AVENUE SOUTH



- PLAN NOTES:
- PIPE INVERT ELEVATION AT THIS APPROXIMATE LOCATION IS 12 INCHES ABOVE ROOF LEVEL.
  - PIPE INVERT ELEVATION AT THIS APPROXIMATE LOCATION IS 22 INCHES ABOVE ROOF LEVEL.
  - PIPE INVERT ELEVATION AT PIPE TEE AT THIS APPROXIMATE LOCATION IS 35 INCHES ABOVE ROOF LEVEL.
  - PIPE INVERT ELEVATION AT INLET CONNECTION TO BLOWER FAN IS 38 INCHES ABOVE ROOF LEVEL.
  - CONTRACTOR SHALL PROVIDE ROOF PIPE SUPPORT SADDLES A MINIMUM OF EVERY 6 FEET FOR PIPE SUPPORT ON ROOF. PIPING ON ROOF SLOPES 1/8" PER FOOT. PIPE SADDLE SUPPORT HEIGHTS VARY. CONTRACTOR SHALL FIELD VERIFY DURING INSTALLATION OF PIPE SADDLE SUPPORTS THE EXACT HEIGHTS FOR EACH SUPPORT SADDLE INSTALLED ON ROOF AS REQUIRED.
  - SEE DETAIL SHEET M4 FOR SUMP INSTALLATIONS SUMP #1 THROUGH SUMP #7.

EXIST. RTU = 80 sq. ft. x 5 = 400 sq. ft.  
EXIST. EF = 4 sq. ft. x 7 = 28 sq. ft.  
EXIST. CU = 9 sq. ft. x 4 = 36 sq. ft.  
EXIST. BV = 1 sq. ft. x 9 = 9 sq. ft.  
EXIST. RV = 2 sq. ft. x 1 = 2 sq. ft.  
EXIST. RD = .5 sq. ft. x 2 = 1 sq. ft.  
NEW BLOWER = 4 sq. ft. x 1 = 4 sq. ft.  
TOTAL APPROX. SQ.FT. = 480 sq. ft.


SCALE: 1/16" = 1'-0"

ROOF AREA = 52,800 GSF  
EXISTING HVAC EQUIPMENT AREA = 476 GSF  
NEW HVAC EQUIPMENT AREA = 4 GSF  
ROOF COVERAGE =  $\frac{EXIST. HVAC (476) + NEW HVAC (4)}{52,800} \times 100\% = .91\%$


NEW REGENERATIVE BLOWER = 83 dBA  
DISTANCE TO CLOSEST PROPERTY LINE = 130 FT.  
dBA REDUCTION FROM EQUIPMENT (TABLE 2) 38 dBA  
NET SOUND LEVEL = 83 dBA - 38 dBA = 45 dBA

PLOT SCALE: 1/4" = 1'-0"







SCALE: 1/4" = 1'-0"



SCALE: 1/4" = 1'-0"



SCALE: 1/4" = 1'-0"



SCALE: 1/4" = 1'-0"


| REGENERATIVE BLOWER SCHEDULE |            |           |                                   |    |         |                     |                     |                          |                   |                      |                        |                                  |                    |
|------------------------------|------------|-----------|-----------------------------------|----|---------|---------------------|---------------------|--------------------------|-------------------|----------------------|------------------------|----------------------------------|--------------------|
| UNIT #                       | BRAND NAME | MODEL #   | MOTOR ENCLOSURE<br>SHAFT MATERIAL | HP | VOLTAGE | PHASE-<br>FREQUENCY | INSULATION<br>CLASS | NEMA RATED<br>MOTOR AMPS | SERVICE<br>FACTOR | LOCKED<br>ROTOR AMPS | MAXIMUM<br>BLOWER AMPS | RECOMMENDED NEMA<br>STARTER SIZE | SHIPPING<br>WEIGHT |
| 1                            | ROTRON     | DR656K72X | TEFC-CS                           | 3  | 230/460 | 3-60-Hz             | F                   | 7.4/3.7                  | 1.15              | 54/27                | 8.8/4.4                | 0/0                              | 114 lb.            |
|                              |            |           |                                   |    |         |                     |                     |                          |                   |                      |                        |                                  |                    |
|                              |            |           |                                   |    |         |                     |                     |                          |                   |                      |                        |                                  |                    |
|                              |            |           |                                   |    |         |                     |                     |                          |                   |                      |                        |                                  |                    |

NOTES:


1. MAXIMUM FLOW: 210 SCFM; MAXIMUM PRESSURE: 106 IWG;  
MAXIMUM VACUUM: 6.39"Hg (87 IWG); CAST ALUMINUM BLOWER  
HOUSING, IMPELLER & COVER, CAST IRON MUFFLER EXTENSION  
& FLANGES (THREADED); PERMANENTLY SEALED BALL BEARINGS;  
INLET & OUTLET INTERNAL MUFFLING.

2. MANUFACTURED BY AMETEK TECHNICAL AND INDUSTRIAL PRODUCTS  
KENT, OHIO 44240 e-mail: rotronindustrial@ametek.com  
internet: www.ametekltd.com


2. REGENERATIVE BLOWER MOTOR TO BE HIGH EFFICIENCY. BLOWER TO MEET 2006  
NON-RESIDENTIAL ENERGY CODE EFFICIENCY REQUIREMENTS AS A MINIMUM.




SCALE: 1/4" = 1'-0"




SCALE: 1/4" = 1'-0"



SCALE: 1/4" = 1'-0"



SCALE: 1/4" = 1'-0"



SCALE: 1/2" = 1'-0"



RADON MITIGATION TESTING AND INSTALLATION  
NORTH 2801 MONROE, SUITE A  
SPOKANE, WASHINGTON  
(509) 326-5127

98108-3248

SEATTLE, WASHINGTON

PROJECT:  
JOB NO.: 6198563  
DATE: 11/07/08  
DRAWN: KJ  
CHECKED: DG

SHEET NO.:


**APPENDIX B**  
**PRESSURE GAUGE SCHEMATIC**

VAPOR INTRUSION, INSPECTION, MONITORING,  
AND MAINTENANCE WORK PLAN


Olympic Medical Facility  
5900 First Avenue South  
Seattle, Washington

Farallon PN: 457-004

## PRESSURE GAUGE SWITCH "ON"



## PRESSURE GAUGE SWITCH "OFF"



### LEGEND



BALL VALVE "OPEN"



BALL VALVE "CLOSED"



PRESSURE GAUGE



FARALLON CONSULTING  
975 5th Avenue Northwest  
Issaquah, WA 98027

PRESSURE GAUGE SWITCH  
OLYMPIC MEDICAL BUILDING  
SEATTLE, WASHINGTON


FARALLON PN: 457-004

Drawn By: DEW

Checked By: DC


Date: 10/30/09

Disk Reference: FLOORJIM21


Series  
2000

# Magnehelic® Differential Pressure Gages

Indicate Positive, Negative or Differential, Accurate within 2%

Patent Nos. 4,030,365  
5,012,678

Standard Magnehelic® Pressure Gage has a large, easy-to-read 4" dial.

Dimensions, Standard Series 2000 Magnehelic® Pressure Gages.  
(Slightly different on medium and high pressure models)

Select the Dwyer® Magnehelic® gage for high accuracy — guaranteed within 2% of full scale — and for the wide choice of 81 models available to suit your needs precisely. Using Dwyer's simple, frictionless Magnehelic® gage movement, it quickly indicates low air or non-corrosive gas pressures — either positive, negative (vacuum) or differential. The design resists shock, vibration and over-pressures. No manometer fluid to evaporate, freeze or cause toxic or leveling problems. It's inexpensive, too.

The Magnehelic® gage is the industry standard to measure fan and blower pressures, filter resistance, air velocity, furnace draft, pressure drop across orifice plates, liquid levels with bubbler systems and pressures in fluid amplifier or fluidic systems. It also checks gas-air ratio controls and automatic valves, and monitors blood and respiratory pressures in medical care equipment.

**Note:** May be used with Hydrogen. When ordering a Buna-N diaphragm pressures must be less than 35 psi.

**MOUNTING.** A single case size is used for most models of Magnehelic® gages. They can be flush or surface mounted with standard hardware supplied. With the optional A-610 Pipe Mounting Kit they may be conveniently installed on horizontal or vertical 1/4" - 2" pipe. Although calibrated for vertical position, many ranges above 1" may be used at any angle by simply re-zeroing. However, for maximum accuracy, they must be calibrated in the same position in which they are used. These characteristics make Magnehelic® gages ideal for both stationary and portable applications. A 4/16" hole is required for flush panel mounting. Complete mounting and connection fittings plus instructions are furnished with each instrument.



Flush ...Surface...or Pipe Mounted

## VENT VALVES

In applications where pressure is continuous and the Magnehelic® gage is connected by metal or plastic tubing which cannot be easily removed, we suggest using Dwyer A-310A vent valves to connect gage. Pressure can then be removed to check or re-zero the gage.

## HIGH AND MEDIUM PRESSURE MODELS

Installation is similar to standard gages except that a 4 13/16" hole is needed for flush mounting. The medium pressure construction is rated for internal pressures up to 35 psig and the high pressure up to 80 psig. Available for all models. Because of larger case, the medium pressure and high pressure models will not fit in a portable case size. Installation of the A-321 safety relief valve on standard Magnehelic® gages often provides adequate protection against infrequent overpressure.



## SPECIFICATIONS

**Service:** Air and non-combustible, compatible gases. (Natural Gas option available.)

**Wetted Materials:** Consult factory.

**Housing:** Die cast aluminum case and bezel, with acrylic cover. Exterior finish is coated gray to withstand 168 hour salt spray corrosion test.

**Accuracy:** ±2% of full scale (±3% on - 0, -100 Pa, -125 Pa, 10MM and ±4% on - 00, -60 Pa, -6MM ranges), throughout range at 70°F (21.1°C).

**Pressure Limits:** -20" Hg. to 15 psig.† (-0.677 bar to 1.034 bar); MP option: 35 psig (2.41 bar), HP option: 80 psig (5.52 bar).

**Overpressure:** Relief plug opens at approximately 25 psig (1.72 bar), standard gages only.

**Temperature Limits:** 20 to 140°F\* (-6.67 to 60°C).

**Size:** 4" (101.6 mm) Diameter dial face.

**Mounting Orientation:** Diaphragm in vertical position. Consult factory for other position orientations.

**Process Connections:** 1/8" female NPT duplicate high and low pressure taps - one pair side and one pair back.

**Weight:** 1 lb 2 oz (510 g), MP & HP 2 lb 2 oz (963 g).

**Standard Accessories:** Two 1/8" NPT plugs for duplicate pressure taps, two 1/8" pipe thread to rubber tubing adapter and three flush mounting adapters with screws. (Mounting and snap ring retainer substituted for 3 adapters in MP & HP gage accessories.)

\*Low temperature models available as special option.

†For applications with high cycle rate within gage total pressure rating, next higher rating is recommended. See Medium and High pressure options at lower left.

## OPTIONS AND ACCESSORIES

### Transparent Overlays

Furnished in red and green to highlight and emphasize critical pressures. ....\$14.25 net

### Adjustable Signal Flag

Integral with plastic gage cover. Available for most models except those with medium or high pressure construction. Can be ordered with gage or separate. .16.75

### LED Setpoint Indicator

Bright red LED on right of scale shows when setpoint is reached. Field adjustable from gage face, unit operates on 12-24 VDC. Requires MP or HP style cover and bezel. ....80.00

### Portable Units

Combine carrying case with any Magnehelic® gage of standard range, except high pressure connection. Includes 9 ft. (2.7 m) of 3/8" I.D. rubber tubing, standhang bracket and terminal tube with holder. ....33.50

### Air Filter Gage Accessory Package

Adapts any standard Magnehelic® gage for use as an air filter gage. Includes aluminum surface mounting bracket with screws, two 5 ft. (1.5 m) lengths of 1/4" aluminum tubing two static pressure tips and two molded plastic vent valves, integral compression fittings on both tips and valves. ....32.25

# Quality design and construction features

**Bezel** provides flange for flush mounting in panel.

**Clear plastic face** is highly resistant to breakage. Provides undistorted viewing of pointer and scale.

**Precision litho-printed scale** is accurate and easy to read.

**Red tipped pointer** of heat treated aluminum tubing is easy to see. It is rigidly mounted on the helix shaft.

**Pointer stops** of molded rubber prevent pointer over-travel without damage.

**"Wishbone" assembly** provides mounting for helix, helix bearings and pointer shaft.

**Jeweled bearings** are shock-resistant mounted; provide virtually friction-free motion for helix. Motion damped with high viscosity silicone fluid.

**Zero adjustment screw** is conveniently located in the plastic cover, and is accessible without removing cover. O-ring seal provides pressure tightness.

**Helix** is precision made from an alloy of high magnetic permeability. Mounted in jeweled bearings, it turns freely, following the magnetic field to move the pointer across the scale.

**O-ring seal** for cover assures pressure integrity of case.

**Blowout plug** of silicone rubber protects against overpressure on 15 psig rated models. Opens at approximately 25 psig.

**Die cast aluminum case** is precision made and iridite-dipped to withstand 168 hour salt spray corrosion test. Exterior finished in baked dark gray hammerloid. One case size is used for all standard pressure options, and for both surface and flush mounting.

**Silicone rubber diaphragm** with integrally molded O-ring is supported by front and rear plates. It is locked and sealed in position with a sealing plate and retaining ring. Diaphragm motion is restricted to prevent damage due to overpressures.

**Calibrated range** spring is flat spring steel. Small amplitude of motion assures consistency and long life. It reacts to pressure on diaphragm. Live length adjustable for calibration.

**Samarium Cobalt magnet** mounted at one end of range spring rotates helix without mechanical linkages.

## SERIES 2000 MAGNEHELIC® GAGE — MODELS AND RANGES

The models below will fulfill most requirements. Page V also shows examples of special models built for OEM customers. For special scales furnished in ounces per square inch, inches of mercury, metric units, etc., contact the factory.

| Model Number | Range, In. W.C. | Range, Pa or kPa | Price   |
|--------------|-----------------|------------------|---------|
| 2000-0D†     | 0-0.5           | 0-125 Pa         | \$63.50 |
| 2001D        | 0-1.0           | 0-250 Pa         | 63.50   |
| 2002D        | 0-2.0           | 0-500 Pa         | 63.50   |
| 2003D        | 0-3.0           | 0-750 Pa         | 63.50   |
| 2004D        | 0-4.0           | 0-1.0 kPa        | 63.50   |
| 2006D        | 0-6.0           | 0-1.5 kPa        | 63.50   |
| 2008D        | 0-8.0           | 0-2.0 kPa        | 63.50   |
| 2010D        | 0-10            | 0-2.5 kPa        | 63.50   |

| Model Number  |       | Range<br>Inches<br>of Water | Price                                       | Model Number | Range<br>Zero<br>Center<br>Inches of<br>Water | Price                    | Dual Scale Air Velocity Units |         |                    | Model Number      | Range,<br>CM of<br>Water | Price              | Model Number          | Range,<br>Pascals | Price |
|---|-------|-----------------------------|---|--------------|---|--------------------------|-------------------------------|---------|--------------------|-------------------|--------------------------|--------------------|-----------------------|-------------------|-------|
| 2000-00N†   | 0-0.2 | \$70.50                     | 2300-0†                                     | 25-0-25      | \$71.50                                       | 2000-00AV†               | 0-25/300-2000                 | \$70.50 | 2000-15CM          | 0-15              | \$63.50                  | Zero Center Ranges |                       |                   |       |
| 2000-00†  | 0-25  | 70.50                       | 2301  | 5-0-5        | 71.50   | 2000-0AV†                | 0-50/500-2800                 | 63.50   | 2000-20CM          | 0-20              | 63.50                    | 2300-60PA†         | 30-0-30               | \$71.50           |       |
| 2000-0†   | 0-50  | 63.50                       | 2302  | 1-0-1        | 71.50   | 2001AV                   | 0-1.0/500-4000                | 63.50   | 2000-25CM          | 0-25              | 63.50                    | 2300-100PA†        | 50-0-50               | 71.50             |       |
| 2001  | 0-1.0 | 63.50                       | 2304  | 2-0-2        | 71.50   | 2002AV                   | 0-2.0/1000-5600               | 63.50   | 2000-50CM          | 0-50              | 63.50                    | 2300-120PA         | 60-0-60               | 71.50             |       |
| 2002  | 0-2.0 | 63.50                       | 2310  | 5-0-5        | 71.50   | 2010AV                   | 0-10/2000-12500               | 63.50   | 2000-80CM          | 0-80              | 63.50                    | 2300-250PA         | 125-0-125             | 71.50             |       |
| 2003  | 0-3.0 | 63.50                       | 2320  | 10-0-10      | 71.50   | For use with pitot tube. |                               |         | 2000-100CM         | 0-100             | 63.50                    | 2300-500PA         | 250-0-250             | 71.50             |       |
| 2004  | 0-4.0 | 63.50                       | 2330  | 15-0-15      | 71.50   | Model Number             | Range<br>MM of Water          | Price   | 2000-150CM         | 0-150             | 63.50                    |                    |                       |                   |       |
| 2005  | 0-5.0 | 63.50                       | Model Number                                | Range<br>PSI | Price   | 2000-6MM†                | 0-6                           | \$70.50 | 2000-200CM         | 0-200             | 63.50                    |                    |                       |                   |       |
| 2006  | 0-6.0 | 63.50                       | 2201  | 0-1          | \$63.50                                       | 2000-10MM†               | 0-10                          | 63.50   | 2000-250CM         | 0-250             | 63.50                    | Model Number       | Range,<br>Kilopascals | Price             |       |
| 2008  | 0-8.0 | 63.50                       | 2202  | 0-2          | 63.50   | 2000-25MM                | 0-25                          | 63.50   | 2000-300CM         | 0-300             | 63.50                    | 2000-1KPA          | 0-1                   | \$63.50           |       |
| 2010  | 0-10  | 63.50                       | 2203  | 0-3          | 63.50   | 2000-50MM                | 0-50                          | 63.50   | Zero Center Ranges |                   |                          | 2000-1.5KPA        | 0-1.5                 | 63.50             |       |
| 2015  | 0-15  | 63.50                       | 2204  | 0-4          | 63.50   | 2000-80MM                | 0-80                          | 63.50   | 2300-4CM           | 2-0-2             | \$71.50                  | 2000-2KPA          | 0-2                   | 63.50             |       |
| 2020  | 0-20  | 63.50                       | 2205  | 0-5          | 63.50   | 2000-100MM               | 0-100                         | 63.50   | 2300-10CM          | 5-0-5             | 71.50                    | 2000-3KPA          | 0-3                   | 63.50             |       |
| 2025  | 0-25  | 63.50                       | 2210*                                       | 0-10         | 106.00  | Zero Center Ranges       |                               |         | 2300-30CM          | 15-0-15           | 71.50                    | 2000-4KPA          | 0-4                   | 63.50             |       |
| 2030  | 0-30  | 63.50                       | 2215*                                       | 0-15         | 106.00  | 2300-20MM†               | 10-0-10                       | \$71.50 | Model Number       | Range,<br>Pascals | Price                    | 2000-5KPA          | 0-5                   | 63.50             |       |
| 2040  | 0-40  | 63.50                       | 2220*                                       | 0-20         | 106.00  |                          |                               |         | 2000-60PA†         | 0-60              | \$70.50                  | 2000-8KPA          | 0-8                   | 63.50             |       |
| 2050  | 0-50  | 63.50                       | 2230**                                      | 0-30         | 139.00  |                          |                               |         | 2000-100PA†        | 0-100             | 63.50                    | 2000-10KPA         | 0-10                  | 63.50             |       |
| 2060  | 0-60  | 63.50                       | *MP option standard<br>**HP option standard |              |   |                          |                               |         | 2000-125PA†        | 0-125             | 63.50                    | 2000-15KPA         | 0-15                  | 63.50             |       |
| 2080  | 0-80  | 63.50                       |   |              |   |                          |                               |         | 2000-250PA         | 0-250             | 63.50                    | 2000-20KPA         | 0-20                  | 63.50             |       |
| 2100  | 0-100 | 63.50                       |   |              |   |                          |                               |         | 2000-300PA         | 0-300             | 63.50                    | 2000-25KPA         | 0-25                  | 63.50             |       |
| 2150  | 0-150 | 63.50                       |   |              |   |                          |                               |         | 2000-500PA         | 0-500             | 63.50                    | 2000-30KPA         | 0-30                  | 63.50             |       |
|   |       |                             |   |              |   |                          |                               |         | 2000-750PA         | 0-750             | 63.50                    | Zero Center Ranges |                       |                   |       |
| Accessories   |       |                             |   |              |   |                          |                               |         |                    |                   |                          | 2300-1KPA          | 5-0-5                 | \$71.50           |       |
| A-299, Surface Mounting Bracket.....\$27.50   |       |                             |   |              |   |                          |                               |         |                    |                   |                          | 2300-3KPA          | 1.5-0-1.5             | 71.50             |       |
| A-300, Flat Flush Mounting Bracket.....23.50  |       |                             |   |              |   |                          |                               |         |                    |                   |                          |                    |                       |                   |       |
| A-310A, 3-Way Vent Valve.....12.75  |       |                             |   |              |   |                          |                               |         |                    |                   |                          |                    |                       |                   |       |
| A-321, Safety Relief Valve.....16.25  |       |                             |   |              |   |                          |                               |         |                    |                   |                          |                    |                       |                   |       |
| A-432, Portable Kit.....33.50   |       |                             |   |              |   |                          |                               |         |                    |                   |                          |                    |                       |                   |       |
| A-605, Air Filter Kit.....32.25   |       |                             |   |              |   |                          |                               |         |                    |                   |                          |                    |                       |                   |       |
| A-610, Pipe Mount Kit.....19.00   |       |                             |   |              |   |                          |                               |         |                    |                   |                          |                    |                       |                   |       |
| Options — To order, add suffix: I.E. 2001-ASF   |       |                             |   |              |   |                          |                               |         |                    |                   |                          |                    |                       |                   |       |
| ASF (Adjustable Signal Flag).....add \$16.75  |       |                             |   |              |   |                          |                               |         |                    |                   |                          |                    |                       |                   |       |
| HP (High Pressure Option).....add \$66.50   |       |                             |   |              |   |                          |                               |         |                    |                   |                          |                    |                       |                   |       |
| LT (Low Temperatures to -20°F).....\$5.20   |       |                             |   |              |   |                          |                               |         |                    |                   |                          |                    |                       |                   |       |
| MP (Med. Pressure Option).....add \$43.75   |       |                             |   |              |   |                          |                               |         |                    |                   |                          |                    |                       |                   |       |
| SP (Setpoint Indicator).....add \$80.00   |       |                             |   |              |   |                          |                               |         |                    |                   |                          |                    |                       |                   |       |
| Scale Overlays — Red, Green, Mirrored or Combination. Specify Locations Add \$14.25 net |       |                             |   |              |   |                          |                               |         |                    |                   |                          |                    |                       |                   |       |

†These ranges calibrated for vertical scale position.

• Accuracy +/-3%. •• Accuracy +/-4%


**APPENDIX C**  
**REMINDER NOTICE TO TENANTS**

VAPOR INTRUSION, INSPECTION, MONITORING,  
AND MAINTENANCE WORK PLAN  
Olympic Medical Facility  
5900 First Avenue South  
Seattle, Washington

Farallon PN: 457-004



## Reminder



Please check periodically to make sure your depressurization system is working by looking at the pressure gages installed on the system. Turn the pressure gauge switch to the **on** position (parallel to the hose) to engage the pressure gage (as shown in photograph). If the pressure indicator needle reads **above** zero then the system is working properly. However, if the pressure indicator needle reads **zero**, then please call me so that we can make arrangements to fix any problems.

Temporary problems with the system would not indicate any health risks – we just need to make sure the system is operating correctly. Please call me if you have any questions.

Thank you for your cooperation,

Dan Caputo  
Project Manager  
Farallon Consulting, LLC  
(425) 295-0800

**APPENDIX D**  
**DEPRESSURIZATION SYSTEM MONITORING LOG BOOK**

VAPOR INTRUSION, INSPECTION, MONITORING,  
AND MAINTENANCE WORK PLAN  
Olympic Medical Facility  
5900 First Avenue South  
Seattle, Washington

Farallon PN: 457-004



# **DEPRESSURIZATION SYSTEM MONITORING LOG BOOK**

## **Appendix D of the Vapor Intrusion, Inspection, Monitoring, and Maintenance Work Plan**

**OLYMPIC MEDICAL FACILITY  
5900 1<sup>st</sup> AVENUE SOUTH  
SEATTLE, WASHINGTON**

**In Accordance with  
AGREED ORDER NO. DE 5348**

**Provided by:  
Farallon Consulting, L.L.C.  
975 5th Avenue Northwest  
Issaquah, Washington 98027  
Farallon PN: 457-004**

**For:  
Mr. Ron Taylor  
Capital Industries, Inc.  
5801 Third Avenue South  
Seattle, Washington**


November 2, 2009

Prepared by:

Daniel Caputo  
Project Chemist

Reviewed by:

Peter Jewett, L.G., L.E.G.  
Principal



## MONITORING INSTRUCTIONS

This Depressurization System Monitoring Log Book was prepared for the use of Olympic Medical personnel while performing monthly monitoring of the depressurization system in accordance with the Vapor Intrusion, Inspection, Monitoring, and Maintenance Work Plan for the Olympic Medical Facility dated November 2, 2009.

Monthly monitoring of the pressure gauges is necessary to ensure that the depressurization system is working properly. Because it is not necessary to record data from every gauge, readings should be taken only from gauges that are easily accessible. A figure showing the location of pressure gauges 1 through 7 is provided on the following pages.


The following steps should be taken at each accessible pressure gauge (see attached Pressure Gauge Diagram):

- Turn the Pressure Gauge Switch to the ON position (parallel to the hose)
- Record the position of the Pressure Indicator Needle in the Pressure Reading column of the Depressurization System Monitoring Log. If the pressure gauge is inaccessible, write "NA"
- Turn the Pressure Gauge Switch to the OFF position

If the pressure indicator needle is positioned between 3 and 10 at all of the pressure gauges, no further action is necessary.

If any of the pressure gauge readings are below 3 or above 10, please contact Daniel Caputo at (425) 295-0800. These readings do not indicate any immediate health risks but arrangements will need to be made to ensure that the depressurization system is operating correctly.

If you have any questions or concerns, please contact Daniel Caputo at (425) 295-0800.




**LEGEND**

----- PROPERTY LINE


----- EXTERIOR BUILDING WALL

PRESSURE GAUGE #7 • PRESSURE GAUGE LOCATIONS

0 50  
APPROXIMATE SCALE IN FEET

|   |   |                |                            |
|---|---|----------------|----------------------------|
| <br><b>FARALLON CONSULTING</b><br>975 5th Avenue Northwest<br>Issaquah, WA 98027 | <b>FIGURE 1</b>   |                |                            |
|   | PRESSURE GAUGE LOCATIONS<br>OLYMPIC MEDICAL FACILITY<br>SEATTLE, WASHINGTON |                |                            |
|   | FARALLON PN: 457-004  |                |                            |
| Drawn By: DEW   | Checked By: DC  | Date: 10/28/09 | Disk Reference: FLOORJIM21 |

## PRESSURE GAUGE DIAGRAM



## DEPRESSURIZATION SYSTEM MONITORING LOG

| Pressure Gauge      | Pressure Reading | Pressure Gauge      | Pressure Reading | Pressure Gauge      | Pressure Reading |
|---------------------|------------------|---------------------|------------------|---------------------|------------------|
| Pressure Gauge #1   |                  | Pressure Gauge #1   |                  | Pressure Gauge #1   |                  |
| Pressure Gauge #2   |                  | Pressure Gauge #2   |                  | Pressure Gauge #2   |                  |
| Pressure Gauge #3   |                  | Pressure Gauge #3   |                  | Pressure Gauge #3   |                  |
| Pressure Gauge #4   |                  | Pressure Gauge #4   |                  | Pressure Gauge #4   |                  |
| Pressure Gauge #5   |                  | Pressure Gauge #5   |                  | Pressure Gauge #5   |                  |
| Pressure Gauge #6   |                  | Pressure Gauge #6   |                  | Pressure Gauge #6   |                  |
| Pressure Gauge #7   |                  | Pressure Gauge #7   |                  | Pressure Gauge #7   |                  |
| <b>Recorded by:</b> |                  | <b>Recorded by:</b> |                  | <b>Recorded by:</b> |                  |
| <b>Date:</b>        |                  | <b>Date:</b>        |                  | <b>Date:</b>        |                  |
| Pressure Gauge      | Pressure Reading | Pressure Gauge      | Pressure Reading | Pressure Gauge      | Pressure Reading |
| Pressure Gauge #1   |                  | Pressure Gauge #1   |                  | Pressure Gauge #1   |                  |
| Pressure Gauge #2   |                  | Pressure Gauge #2   |                  | Pressure Gauge #2   |                  |
| Pressure Gauge #3   |                  | Pressure Gauge #3   |                  | Pressure Gauge #3   |                  |
| Pressure Gauge #4   |                  | Pressure Gauge #4   |                  | Pressure Gauge #4   |                  |
| Pressure Gauge #5   |                  | Pressure Gauge #5   |                  | Pressure Gauge #5   |                  |
| Pressure Gauge #6   |                  | Pressure Gauge #6   |                  | Pressure Gauge #6   |                  |
| Pressure Gauge #7   |                  | Pressure Gauge #7   |                  | Pressure Gauge #7   |                  |
| <b>Recorded by:</b> |                  | <b>Recorded by:</b> |                  | <b>Recorded by:</b> |                  |
| <b>Date:</b>        |                  | <b>Date:</b>        |                  | <b>Date:</b>        |                  |

**APPENDIX E**  
**INSPECTION FORM**

VAPOR INTRUSION, INSPECTION, MONITORING,  
AND MAINTENANCE WORK PLAN  
Olympic Medical Facility  
5900 First Avenue South  
Seattle, Washington

Farallon PN: 457-004



## Form 1 - Sub-Slab Depressurization System Inspection Form

Date: \_\_\_\_\_ Time: \_\_\_\_\_

Address: \_\_\_\_\_

### PART 1 - DOCUMENTATION OF CONDITION OF SYSTEM COMPONENTS

|   |   |   |     |
|---|---|---|-----|
| Exterior Pipe Free of Cracks                                      | Y | N | N/A |
| Interior Pipe Free of Cracks                                      | Y | N | N/A |
| Fan Running Appropriately (no excess vibration or noise)          | Y | N | N/A |
| Caulk on Floor Penetrations in Good Condition                     | Y | N | N/A |
| Manometer in Good Condition                                       | Y | N | N/A |
| Significant basement floor cracking, or new openings in the floor | Y | N | N/A |
| Significantly different manometer/pressure gauge readings         | Y | N | N/A |
| All PFE test locations effectively capped/plugged                 | Y | N | N/A |
| Riser valves (between each riser and gauge) operating properly    | Y | N | N/A |

#### Manometer/Pressure Gauge Readings

| Date | In.H <sub>2</sub> O |
|------|---------------------|
|      |                     |
|      |                     |
|      |                     |
|      |                     |
|      |                     |
|      |                     |
|      |                     |
|      |                     |
|      |                     |

### PART 2 - DOCUMENTATION OF STRUCTURAL CHANGES

|   |   |   |     |
|---|---|---|-----|
| Any Significant changes to the building's HVAC System   | Y | N | N/A |
| Any new vents or openings in the roof/walls, less than 10' away from the stack (and <2' below it)               | Y | N | N/A |
| Any changes to the use of any chimneys that could result in re-entrainment                                      | Y | N | N/A |
| Any new buildings near the mitigated building close enough that stack gasses could contaminate their indoor air | Y | N | N/A |
| Has the attic been remodeled into a living space (if the mitigation fan is located in the attic)                | Y | N | N/A |
| Have there been any <i>significant</i> earthquake events  | Y | N | N/A |
| Significantly different manometer/pressure gauge readings   | Y | N | N/A |

### PART 3 – OTHER OBSERVATIONS/COMMENTS

---



---



---



---



---

Inspected by: \_\_\_\_\_ (Signature) \_\_\_\_\_ (Printed Name)